

# 1 Integrated Automated/Robotic On-site Factories

In this volume all worldwide conducted approaches following an on-site factory approach were analysed. Thirty different systems were identified, resulting in an application of automated/robotic on-site factory technology about 60 times. The analysis was for each system split into a more technical part and a part that focuses on indicators related to productivity, efficiency, and economic performance. All systems were analysed systematically and based on the same framework. On the basis of the analysis, a categorization system was developed and 13 categories were set up (10 categories for construction and 3 for deconstruction).

As discussed in **Volume 3**, one of the main ideas for setting up automated on-site factories was to integrate stand-alone or single-task construction robot (STCR) technology in structured on-site environments into networked machine systems and thus to improve through interlinked machine activities the organization, integration, and material flow on the construction site (apart from the possibility to off-site manufacture components discussed in **Volume 2**). The analysis clarifies for which building typologies automated/robotic on-site factories are an applicable approach and how and to which extent each of those systems is technologically flexible to be able to manufacture a variety of different buildings (products) on the basis of industrialized, automated, and flow-line-like stable factory processes on the construction site. Furthermore, it should be clarified whether, in contrast to the STCR approach (see **Volume 3**), the approach of setting up automated/robotic on-site factories is capable of achieving a performance multiplication (e.g., by 10-fold as in tunneling or automotive industry; for further details see **Volume 1**), which usually accompanies the switch from arts and crafts-based manufacturing to machine-based manufacturing.

In this volume, first, frameworks for the technical analysis and the efficiency analysis classified into various fields, analysis subjects, and indicators are set up. Second, 30 systems are analysed according to the technical analysis framework and classified into two main categories (construction: 24, deconstruction: 6) and a total of 13 sub-categories. Ten of those systems are also analysed with regard to analysis subjects and indicators that determine or influence productivity, efficiency, and overall economic performance. An *Analysis and Categorization Matrix* (see Figure 2.35) gives an overview over systems, categories, analysed analysis subjects and indicators, and available data. Finally, the findings are summarized (see Chapter 4). The analysis

claims to include all approaches to automated/robotic on-site factories that were conducted so far.

**1.1 Framework for Technical and Efficiency Analysis**

In this volume, the technical aspects of integrated automated construction sites (including their composition and configuration), as well as their resulting efficiency, are analysed. Automated construction sites represent on-site manufacturing (ONM) environments (fixed type or moving type) that conduct a final assembly of low-, medium-, and high-level modular components rather than a conventional construction process. The installation of a factory on-site structures the work environment and allows the application of automation and robot technology. Furthermore, the processing of value-added components designed according to robot-oriented design (ROD) strategies reduces on-site complexity. The modularization of both building products and manufacturing systems allows for flexibility and customisation of the products (buildings) to a certain degree. The technical analysis follows the identification of concepts and strategies relevant to the fields of multilevel modularity (see **Volume 1, Section 4.2**), manufacturing technologies and strategies (see **Volume 1, Section 4.3**), and automation and robot technology (see **Volume 1, Section 4.4**). An overview of the framework developed for the technical and configuration analysis is presented in Table 1.1. The data used in this analysis were acquired from various sources such as project descriptions by the companies, publications by companies and their R&D staff, publications by researchers who had analysed systems, expert interviews with developers and company staff, and own site visits. Furthermore, as a basis for the analysis, documentary material in the form of plans, project descriptions, and an own picture archive documenting the application of nearly all systems were used.

As far as efficiency and productivity are concerned, the analysis framework is based on the assumption that technical and economic efficiencies are generated by both an efficient combination of input factors and the set-up of a high-value product with a low defect rate. Individual performance indicators, such as work productivity, material efficiency, physical strain, health and safety, construction quality (related to the defect rate), and integration along the value chain have been identified as the most influential construction performance indicators (see **Volume 1**). In addition, as outlined in **Volume 1**, the construction industry is highly labour intensive, with decreasing labour productivity, a high rate of construction defects, a high rate of fatal and nonfatal injuries, and a relatively high amount of material input compared to the output value. This correlates with the low investment and R&D spending rate and the low capital stock, indicating that the value and quality of the existing manufacturing equipment, process technologies, and skilled workforce are low. However, integrated automated construction sites would require, for example, as in the automotive industry, a high investment and R&D spending rate, a high level of capital stock, and in that context of course demand for considerable improvements in the aforementioned performance indicators. The efficiency analysis for each system attempts to analyse whether integrated automated site technology has the potential to deliver the demanded efficiency improvements. The technical configuration of the systems and their efficiency are closely related to each other. In most cases, positive

Framework for Technical and Efficiency Analysis

Table 1.1. Framework for the analysis of technical aspects and system configuration

Field of analysis	Analysis subjects and indicators
Evolution scheme	Location of sky factory and ground factory Working direction General workflow
Elevation	Detailed vertically organized workflow Parallel work on various levels Configuration of main and sub-factories Analysis of the component installation process
Ground plan (main and sub-factory)	Detailed horizontally organized workflow Configuration of main and sub-factories
Subsystems	SF (covered, working platforms, closed sky factory, open sky factory) Vertical logistics (in particular vertical delivery systems) Horizontal logistics (in particular horizontal delivery systems) Manipulators (in particular overhead manipulators) Climbing mechanisms (in particular climbing systems) Assembly simulation and progress control tools (real-time monitoring and management system and material handling, sorting, and processing yard)
End-effectors	Types of end-effectors Relation of end-effectors and components/materials Modularity Possibility of tool changes
System variations	Realized system variations Possible system variations Inbuilt flexibility Modular flexibility
Robot-oriented design (ROD)	ROD on a component level ROD on a building level ROD on an urban level

or negative efficiency performance can be directly correlated to the general set-up, configuration, use of subsystems/end-effectors, and the deployment of ROD.

The analysis framework for the systems’ efficiency was synchronized with the currently available data sets. Analysis subjects that companies deploying the systems did not analyse or make available (e.g., detailed data on investment or defects/errors, or injuries related to the application of the new technology) were not considered in the framework. The *Analysis and Categorization Matrix* (see Figure 2.35) shows which data were made available for each system. Obviously, companies that deploy their systems more often than others (Obayashi, Shimizu) also generate or are interested in generating more data sets. Table 1.2 outlines the analysis framework and shows which analysis subjects and indicators were considered as relevant for the efficiency analysis.

All of the data presented have to be considered from the perspective that all systems were still in an experimentation, prototype or test phase. With the development of such technologies, Japanese companies have aimed at long-term efficiency





















4 Integrated Automated/Robotic On-site Factories

Table 1.2. Efficiency analysis framework

Thematic field	Analysis subjects	Indicators
Erection speed	Project schedule	Time necessary to set up a sky factory Operation period Time necessary for dismantling of a sky factory
	Floor erection cycle	Floor production rate per month Time and work steps necessary to complete a standard floor Parallel processing on several floors Equipment (e.g., overhead manipulator) operation sequence
Configuration	Technical data speed of equipment	Operational speed of horizontal delivery system Operational speed of climbing system Operational speed of vertical delivery system
	Experiment's degree of automation/system configuration/worker teams	Rate of automation – is installation operation remote controlled, partly automated, or fully automated? Could companies apply system in various configurations (flexibility) Influence of varying numbers of workers, e.g., on productivity
Productivity	Productivity workers/time (including comparisons with conventional construction or other systems)	Man-hours required for completion of floor Number of construction workers required for a specific task field Total number of workers Comparison with conventionally constructed buildings
	Learning effects	Reduction of time needed to install components with the novel site technology/equipment Reduction of time needed for welding Reduction of time required for factory internal logistics
Resource efficiency	Material and resource efficiency	Reduction of required input material Reduction of construction waste generated
Quality, health and safety	Product or process monitoring (real-time progress, decibel, etc., control room)	Real-time supervision of operations Real-time progress control, real-time monitoring and management system Simulation of optimized operation
	Safety Physical strain (heart rate, etc.) Weather influence	Influence of environment on safety Influence of environment on physical strain Influence of weather on: <ul style="list-style-type: none"><li>• Operation/task execution</li><li>• Productivity</li><li>• Quality</li></ul>
Usability studies	Evaluation of usability of on-site factory and equipment by workers/operators	Influence on work tasks Influence on motivation Influence on user acceptance and emotions

and at building up knowledge step by step, and thus made a number of compromises concerning short-term efficiency. Obayashi and Shimizu, for example, each of which deployed their systems in a multitude of construction projects (ABCS: applied six times; Big Canopy: applied six times; SMART: applied six times), introduced improvements in each new project and experimented with the configuration of the robotic crane systems or with the automation degree and the number of workers used (and thus the degree of work productivity). For example, during the first projects using the SMART, Shimizu had the intention of training its workforce on the general use of the new technology (according to Japanese philosophy, knowledge about new technologies and tools has to be spread fast among the workforce by special training procedures), and thus replaced half the workforce with new workers from project to project to train as many of their workforce in using the new technology as quickly as possible. Considering the fact that the learning effects within projects were enormous (see later in the efficiency analysis of the SMART system in Chapter 2), it can be assumed that this procedure influenced efficiency considerably, as it mitigated the impact of these learning effects across projects. Furthermore, most systems were still in a developmental phase, and did not fully utilize the capacity of their subsystems at any time during individual projects. Shimizu, for example, had up to 24 robotic trolleys (that can potentially be operated in parallel) available in a fully deployed SMART, but operated some projects with, for example, only 10 of them in an active mode.

Analysis and Categorization Matrix

Construction by Automated/ Robotic On-site Factory																
Sky Factory (moving upwards) supported by building								Sky Factory (moving upwards) on stilts (prolonging)		Sky Factory pulled up along core (main factory and core factory moving upwards)		Ground Factory (staying fixed place, vertically oriented building) and building push-up		Ground factory (staying fixed place, horizontally oriented building) and building push-up		
Category 1								2		3		4		5		
																
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15		
																
Advanced Building Construction System (ABCS)	Asakura 21	Future Advanced Construction Efficient System (FACES)	Mini Climbing Construction System (MCCS)	Roof Push-up	Roof Fibro	Shimizu Manufacturing System by Advanced Technology (SMART)	System Netherlands	Big Canopy	SMART Light	Totally Mechanised Construction System (TUG)	Robotic and Crane based Automatic Construction System (RACAS)	Automatic Up-Rising Construction by Advanced Technique (AUIATD)	System Skanska	AUP		
Technical Analysis	Factory Layout (Evolution Scheme, Elevation, Ground Plan)	Location of main factory	On top	On top	On top	On top	On top	On top	On top	On top	On top	On top	On ground	On ground	On ground	
	Working direction	Vertically upwards	Vertically upwards	Vertically upwards	Vertically upwards	Vertically upwards	Vertically upwards	Vertically upwards	Vertically upwards	Vertical upwards	Vertical upwards	Vertical upwards	Push up vertical	Push up vertical	Push up vertical	
	Building Material Main Structure	Steel	Steel	Steel	Steel	Steel	Steel	Concrete	Concrete	Concrete	Steel	Steel	Concrete	Concrete	Steel	
	Main Factory Cover Structure	x	x	x	x	x	x	x	x	x	x	x	x	x	x	
	Vertical Delivery System		x			x	x		x	x		x	x			
	Horizontal Delivery System		x		x	x	x	x	x	x	x	x	x	x		
	Vertical/Horizontal Delivery System	x		x		x	x	x	x	x	x	x	x			
	Number of Overhead Manipulators	3	3	2	2	2	2	Up to 25	2	Up to 3	Min. 3	2	2	3	1	
	Climbing System (or push-up/sliding)	x	x	x	x	x	x	x	x	x	x	x	x	x	x	
	Dedicated Facade Installation System	x														
	Sub-factory (storage, component preparation)		x				x	x		x	x		x	x	x	
	Column Welding Subsystem	x		x	x			x								
	Beam Welding Subsystem	x														
	Logistics Robots for Interior Finishing	x					x				x		x			
	Other Robots for Interior Finishing					x	x	x				x				
	Material Management System	x	x	x	x				x		x	x	x	x	x	
	Real Time Monitoring System	x	x	x	x	x	x	x	x	x		x	x	x		
	Component Alignment System	x		x	x	x	x				x					
	Construction Process Simulator	x		x				x		x			x			
	End-effectors	Number of Sub-systems	10	12	7	12	9	10	8	5	7	6	13	6	9	8
Number of End-effectors		6	4	7	1	1	1	1	2	2	1	4	>1	7	1	
In-built Flexibility (+, ++, +++)		+	+	+	+++	+++	+++	+++	+++	++	+++	++	+	++	+++	
Modular Flexibility (+, ++, +++)		+++	+++	+++	+	+	+	+	+	++	+	++	+++	+	+	
System Variations	Number of applied and planned Variations	4	2	2	2	1	1	6	1	3	2	6	1	3	1	
	ROD on component level	x	x	x	x	x	x	x	x	x		x	x	x	x	
Robot Oriented Design (ROD)	ROD on building level						x					x	x		x	
	ROD on urban level															
	ROD on building level															
Erection Speed	Total on-site construction time necessitated	6-24 month		15 month						2 years		20 month		10 month	2-4 month	
	Time necessitated for system set up	1 month	2 month	2-5 month	1-2 month	1-2 month	1-2 month	2-3 month	1 month		6 weeks		6 weeks		1 day	
	Time necessitated for system dismantling	2-3 weeks	2 weeks	1 month	2-3 weeks	2-3 weeks	2-3 weeks	1-2 month	1 month		2 weeks		2 weeks		1 day	
	Floor Erection Cycle	5/6 days	9 days	6 days	6-8 days	5,5 days	6-8 days	5/6 days	14 days	7 days	about 10 days		3 days	6 days		
	Number of Floors produced per month	4	2-3	2,5	2-3	2-3	2-3	about 3	1-2	2,7	2	2,4		2	1-2	
	Start of operation from floor X	3	3	0	2	3	4	1		3	0	5-6	1	2	1	
	Parallel work levels	>4	3	>4									6			
	Levels enclosed by Sky Factory	3	3	4									3			
	Configuration	Speed of equipment	40 m/min	20-25 m/min	20 m/min	20-25 m/min	20-25 m/min	20-25 m/min	20-40 m/min		40 m/min	20-40 m/min		10 m/min	10-20 m/min	
		Automation ratio	Automatic/ remote	Automatic/ remote	Automatic/ remote (automatic mode was slower)	Automatic/ remote	Automatic/ remote	Automatic/ remote	Remote controlled	Full automation and remote operation possible (remote 10% faster)	Remote	Automatic/ remote	Automatic/ remote	Automatic/ remote	Automatic/ remote	Remote
Task specific work productivity				Improvement of work productivity by the two to six fold				Manhours reduced by 50%, number of workers reduced by 30%								
Productivity	Total labor productivity							Time necessary to construct the building reduced by about 15%,		Up to 70% less workers		Manhours 68% reduction, construction time: 20% reduction		Improvement of labor productivity of up to 50%, reduction of construction time up to 30%		
	Learning effects	Component installation 10%, welding 20%						20 % for column positioning		Up to 20%				40-50% for standard floor		
	Measurements to reduce consumption/ waste							70% waste reduction		50% waste reduction						
Resource Efficiency	Multiple working platforms	x	x	x	x	x		x	x				x			
	Protection in terms of	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	
Quality, Health and Safety	Protection in terms of	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	
Usability	Usability aspects	Positive influence of protected environment		Attract skilled workers by technology				Attract skilled workers by technology		Measurable decrease of heart-rate of workers						

								De-construction by Automated/ Robotic On-site Factory							
Off- and on-site combined factory (both off and on-site factory fixed place)		Self-supported Ground Factory (horizontally moving)		Sky Factory (moving upwards) for simple tower manufacturing		Centralized Sky Factory (moving upwards) in combination with conventional construction		Decentralized Sky Factory (moving upwards) in combination with conventional construction		Closed Sky Factory supported by building (moving downwards)		Open Sky Factory supported by building (moving downwards)		Ground factory (fixed place) and building lift-down	
6		7		8		9		10		11		12		13	
16	17	18	19	20	21	22	23	24	25	26	27	28	29	30	
NCC	Summerfield	Newfert	Taisei	Shimizu	Obayashi	Shimizu	Obayashi	Shimizu	Takenaka	Taisei	Nishimatsu	Shimizu	Obayashi	Kajima	
NCC Complet	Bauchwerkfabrik	Hausbaumaschine	TS-Up	Tower SMART	Hybrid-AWS	Hybrid-SMART	Large Deployment of Tower System (e.g. Tokyo Sky Tree)	Large Deployment of Tower System (e.g. Midek Tower, Cocoon Tower)	Ha Down	Taisei Ecological Reproduction System (TECOSR)	Wave Let	Rover-K Construction Method (RCM)	Quikroof Quicr... Disassembly (Cut-off Method)	Cut-and Take Down Method "Dyna-Umst" (SALUWA)	
Covers Vertical/Horizontal	Covers building	Covers building	On top	On top	On top	On top	Distributed	Distributed	On top	On top	On top	On top	On top	On top	On ground
Concrete	Concrete	Concrete	Steel	Steel	Steel	Steel	Steel	Steel	Steel/ concrete	Steel/ concrete	Steel/ concrete	Steel/ concrete	Concrete	Concrete	Concrete
x	x	x	x	x	x	x			x	x	x	x	x	x	x
x	x	x		x			x	x							x
x			x		x	x	x	x	x		x	x	x		
2	2	6-20	-	1	3	x	Up to 25	-	-	>3	>2	>2	-	-	-
	x	x	x	x	x	x			x	x	x	x	x	x	x
x						x		x	x	x	x				x
					x	x		x	x	x	x				x
x					x	x		x	x	x	x				x
						x							x		
						x	x	x							
6	4	5			10	9	7	6	6	6	5	5	5	5	7
1	3	2	1	1	6	1	1	2	1	1	1	-	-	-	
+++	+	+	+	+	+	++	+++	++							
+	+	x	+	+	+++	+	+	++							
2	3	1	1	1	3	2	>4	>4	1	2	2	2	2	2	2
x	x	x	x	x	x	x		x							
x	x	x	x	x	x	x									
3-6 month					6-24 month				6 month	1 year	Same as conv. construction	Same as conv. construction	Same as conv. construction		6 month
2 weeks					1 month	1-2 month									
1 week					2-3 weeks	2-3 weeks									
2-4					5/6 days	5/6 days			6-10 days	6-10 days	6-10 days	6-10 days	6-10 days	6-10 days	6-10 days
-1	0	0	2	2	3	1	0	0	1	1	0	0	0	0	-
					>4										
20-40 m/min					20-40 m/min	40 m/min	20-40 m/min	40m/min	20-40 m/min						
Remote	-	-	Remote	Remote	Automatic / remote	Automatic / remote	Automatic / remote	Automatic / remote	Remote	Remote	Remote	Remote	Remote	Remote	Remote
						Manhours reduced by 50%, number of workers reduced by 30%									
NCC aims at enhanced productivity (e.g. 4-6 buildings per worker per year			Shortening of construction time by 20%	Shortening of construction time by 20%	Component Installation 10%, Welding 20%	Time necessary to construct the building reduced by about 55%.									
					70% waste reduction				> 90% recycling rate						96 recycling rate
Sun, wind, temperature, rain, sound	Sun, rain	Sun, wind, temperature, rain, sound	Wind	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound	Sun, wind, temperature, rain, sound		Sun, wind, sound	Sun, wind, temperature, rain, sound, dust	Sun, wind, temperature, rain, sound, dust	Wind, sound, dust	Wind, sound, dust	Wind, sound, dust	Sun, wind, temperature, rain, sound, dust	
Heated environment enhanced work speed and motivation					Positive influence of closed environment of coneraction	attract skilled workers by technology			Safe deconstruction environment	Safe deconstruction environment					

## 2 Analysis and Categorization: Construction

Integrated automated construction sites can be categorized according to various features or characteristics, such as general working directions, logistics strategies, climbing mechanisms, or configurations of the site factories. It is also possible to characterize them according to manufacturing views (organizational view, product variation view, order-oriented view, or location-oriented view; for further information, see **Volume 1**). Furthermore, a categorization could also be based on the main building materials processed (steel-based components, concrete-based components). However, the general working direction and thus the location and workflow orientation of the factory and the location of the majority of work activities play a major role in manufacturing of buildings and determine logistics strategies and factory configurations (see **Volume 1**). As buildings are complex and large products (similar to aircrafts or tunnels; see **Volume 1**) that require a final assembly on the fixed, final site (see **Volume 1**), the orientation of the building and thus the location and working direction on-site determine the general organizational setting and thus the logistics strategy, climbing system (CS), and factory configuration. In this chapter a combined location and working-direction-oriented view is used as the basis for categorization.

A location and working-direction-oriented view on manufacturing considers the location or environment in which the product is manufactured as well as its geometrical characteristics. Usually, a product can be manufactured off-site in a factory some distance from the final location to which the finished product is finally shipped and used, as the product in its final state is still a mobile entity (a kind of large module) for which a transport infrastructure exists. Most complex products, such as ships, automobiles, aircraft, and most consumer products can be produced that way. It is no problem to pack and ship them.

However, products such as buildings, towers, bridges, and so forth have to be produced on-site at the location at which they will finally be used and they simply cannot be moved or shipped as a complete entity. High-level component manufacturers or unit manufacturers such as Sekisui Heim circumvent the need for on-site production by splitting up a building into three-dimensional high-level modules that are then produced and finished in the factory so that only minor work (in the case of Sekisui Heim 15–20%; presented in detail in **Volume 2**) has to be done on the construction site. The automated construction system AMURAD, for example, follows a different



strategy and produces the building by an automated/robotic assembly system on the final site and at a fixed place (on-site manufacturing [ONM], fixed-site type; see also Section 2.4.1) by using not high-level but low- to medium-level precast and prefabricated components. The prefabricated components are delivered just in time and just in sequence from an informationally integrated precast plant. Similarly, the erection of a tunnel by a tunnel boring machine (TBM; see also **Volume 2**) with a mechanized or automated component/segment assembly system is an on-site production directly linked to off-site manufacturing (OFM) in the form of the delivery of prefabricated concrete segments. Unlike AMURAD, however, a “TBM factory” is moving and contains element of a production line on-site (moving type). The AMURAD on-site factory system stays during operation more or less at a fixed location (fixed-site type) and “extrudes” the building. In the case of ABCS the factory moves upwards and, in the case of Sommerfeld’s factory system, it moves horizontally to produce the building.

Civil engineering construction sites in tunnelling are also referred to as “line construction sites”. The strict organization of all work activities along an axis or line simplifies systemic workflow organization and (finally) permits mechanization or automation by TBMs (for further details, see **Volume 1**). However, building construction and the floor-by-floor direction that the erection of a building follows demand more complex logistics and work procedures. Whereas a TBM can erect the main structure of a tunnel with one erector placing the segment, the erection of a main structure of a building or floor (columns, beams, floor slabs etc.) requires both a better integration of vertical (along the main direction) or horizontal (along the sub-direction) active logistics and component positioning processes and thus higher flexibility with regard to kinematics and end-effectors due to higher variability.

In addition to the main factory (e.g., sky factory [SF]), many companies deployed a sub-factory (e.g., on ground), where parts and components delivered to the site are stored (intermediate or buffer storage), assembled into more complex components, or prepared for lifting to and processing by the main (sky) factory (e.g., Akatuki 21). The advantage of this approach is that parts and lower level components (can be stored in a compact way on the transport system) can be transported to the site more efficiently than complex and larger components (often demand that due to size and placement in templates a considerable amount of air is shipped). Although the logistics strategy, in terms of efficiency of the systems, might be a key element, it was not be considered as a basis for the categorization, as this strategy can basically be applied to any automated construction site and thus is not a unique characteristic. However, whenever companies have used sub-factories the approach was carefully analysed.

The analysis showed that some deconstruction systems working with downwards moving SFs also utilized the ground floors of a building as a sub-factory/ground factory (GF) where high-level components coming from the SF were processed into low-level components or mono-material for efficient transport to the recycling facilities. ONM systems share a need to be highly mobile, modular, easy to deploy, and dismountable as they are only temporarily installed. For example, Shimizu has developed a simulator for the SMART for optimizing the configuration, installation, and disassembly of the factory on a specific site and for a specific building.

Compared to OFM systems, so far ONM systems tend to have a lower efficiency and lower degrees of automation. A reason for this is that up to date usually a relatively long time is needed to set up the site factory and the complex and relatively heavy on-site automation and robot systems that were still in a developmental phase required slow and careful operation. However, current trends in automation and robot technology, such as modularity, plug-and-play, and lightweight design, have the potential to overcome these obstacles and lower the barrier to entry (for further discussion of the capability of automation and robot technology, see **Volume 1**).

Some companies also have tried to avoid the necessity for disassembly of the on-site factory (e.g., Obayashi, ABCS) by integrating the frame of the factory as a frame for the final floors into the building after completion. Taisei's deconstruction system tries to avoid both the assembly and the disassembly of the on-site factory by utilizing one of the top floors of the building as a factory ceiling and the basis for the installation of overhead manipulators (OMs).

**2.1 Sky Factory (moving upwards) – Supported by Building**

Systems in this category are based on the erection of an SF on top of the building to be constructed. The buildings are assembled from bottom to top. In the SF the building is assembled floorwise and the newly constructed floors are used as the supporting structure that the climbing mechanism of the SF uses to raise the factory upwards.

Three types of climbing mechanisms can be identified:

1. The factory climbs using stilts that use the vertical column structure as support (ABCS, Akatuki 21, FACES, MCCS, Roof Push-up, Roof-Robo).
2. The stilts carrying the factory are supported not by resting on top of individual columns but by using a bridging system and fixing them in between columns and on beams connecting the columns (SMART).
3. The factory rests on the building through girder framework bridges (System Netherlands).

Climbing mechanisms type 2 and type 3 have the advantage that the positioning and fixation of columns on top of other columns is not hindered by the climbing mechanism. However, climbing mechanism type 1 can be used as a fixture or jig, which helps to guide components to be positioned (e.g., columns) into place. Some systems are based on the idea of using a GF (assembly of low-level components to medium or high-level components; Akatuki 21, Roof-Robo) and others focus more on the direct pick-up of components from trucks. However, numerous systems are tried from application to application, and basically all systems in this category have the potential of using GF, direct pick-up, or a combination of both approaches. Systems in this category also vary considerably with regard to the type of main manipulators (automatic/robotic logistics and positioning systems) used.

While some companies build on a reduced number of high-capacity, large and heavy (but highly accurate) manipulators (e.g., FACES), others follow the strategy of distributing complexity and build on a multitude of smaller and faster manipulators that can be operated in parallel (e.g., SMART). A further characteristic of systems in